

REDLINE Asphalt Paver



DRF25 - 60W

Technical Data



Dimensions	
Transport width incl. DRV60 TVE	3 m
Transport length	6.1 m
Transport height	3.10 m
Max. working width	6.7 m
Weight incl. DRV60 TVE	17.5 t
Weight incl. DRV51 TVE	17.2 t
Capacity	
Theoretical placement capacity	650 t/h
Placement thickness (max)	300 mm
Max. paving level below zero	-100 mm
Material hopper	
Capacity	6m ³
Hopper width, external	3250 mm
Dumping height (center/outside)	555/590 mm
Separate hopper control	Yes
Conveyor	
Conveyor type	Dual bar feeder
Conveyor width	2 x 580 mm
Conveyor control	2 independent conveyors with limit switches and speed control
Operation	
Operator console	Ergonomic dashboard with toggle switches, Slideable left/right
Platform	Dual seat concept with foldable canopy

Engine	
Type	6 cylinder watercooled diesel engine with hydrostatic fan drive
Manufacturer	Cummins
Type	QSB 6.7 - C173
Rated power	129kW (175hp) @2200 rpm
Emissions according to	Tier 3
Electrical system	24V
Fuel tank capacity	315 L
Undercarriage	
Final Drive	Direct drive over transmissions
Tyre Size	445/80R25
Front wheels	4 x 560/300 - 390
Wheel drive	2 x rear wheels, 2 x front wheels
Turning radius (inside)	2.48 m
Turning radius (outside)	6.07 m
Paving speed	up to 30 m/min
Transport speed	up to 15 km/h
Ramp up angle front	17°
Auger	
Auger diameter	380 mm
Auger height adjustment	Mechanic
Auger control	2 independent augers with Ultrasonic sensor and proportional speed control
Reversible rotational	Yes
Auger height adjustment	Infinetely variable by 250mm



We reserve the right to change specifications without notice. Photos and illustrations do not always show standard versions of machines.

The above information is a general description only, all information are supplied without liability.

Screeds	Basic width	Hydr. Extendable up to	Max. working width	Compaction	Heating	Weight
DRV51TVE	2.55 m	5.10 m	6.6 m	Tamper Vibration	Electric	3400 kg
DRV60TVE	3.00 m	6.00 m	6.7 m	Tamper Vibration	Electric	3850 kg