

# REDLINE ASPHALT ROLLER

## DRA30

### Technical Data

#### Masses

|                                     |                   |
|-------------------------------------|-------------------|
| Max. operating mass                 | 3200 kg           |
| Operating mass (incl. ROPS)         | 3100 kg           |
| Maximum operating mass (front/rear) | 1500 kg / 1600 kg |

#### Dimensions

|                                   |         |
|-----------------------------------|---------|
| Drum width                        | 1200 mm |
| Height                            | 1836 mm |
| Height with optional canopy /ROPS | 2650 mm |

#### Compaction

|                                 |                   |
|---------------------------------|-------------------|
| Static linear load (front/rear) | 12.5 / 13.3 kg/cm |
| Nominal amplitude               | 0.5 mm            |
| Centrifugal force               | 27 kN             |
| Vibration frequency             | 58 Hz             |
| Water tank volume               | 160 l             |





#### Engine

|                    |                     |
|--------------------|---------------------|
| Manufacturer/Model | Dynapac             |
| Type               | 3 cyl, water cooled |
| Rated power        | 39 hp @ 2600 rpm    |
| Electrical system  | 12 V                |
| Fuel tank capacity | 50 l                |

#### Traction

|                               |                |
|-------------------------------|----------------|
| Speed range                   | 0 - 12 km/h    |
| Theoretical max. gradeability | 38 %           |
| Vertical oscillation          | +/- 10°        |
| Steering angle                | +/- 29°        |
| Turning radius (inner/outer)  | 2900 / 4100 mm |



We reserve right to change specifications without notice. Photos and illustrations do not always show standard versions of machines.

The above information is a general description only, all information are supplied without liability.

