

# REDLINE ASPHALT TANDEM ROLLER



## DRA90

### Technical Data

#### Masses

Operating mass (incl. Canopy)	9200 kg
Maximum operating mass	9600 kg
Module mass (front / rear)	4600 kg / 4600 kg

#### Dimensions

Drum width	1690 mm
Drum diameter	1220 mm
Static linear load	27.2 kg/cm
Wheel base	2785
Dimension (LxWxH) with Canopy	4340 x 1885 x 3140 mm
Drum shell thickness	17 mm
Curb Clearance	370 mm

#### Engine



Manufacturer/Model	Dynapac
Type	4 cyl, water cooled and turbocharged engine
Rated power	56 kW (76 hp) @ 2200 rpm
Electrical system	12 V
Fuel tank capacity	180 l

#### Traction

Speed range	0 - 12 km/h
Vertical oscillation	+/- 7°
Theoretical max. gradeability	39 %
Steering angle	+/- 28°

#### Compaction

Centrifugal force	130/60 kN
Nominal Amplitude	0.9/0.4 mm
Static Linear load (Front/Rear)	27.2 Kg/cm
Vibration Frequency	36/54 Hz
Water tank volume	800 ltrs



We reserve right to change specifications without notice. Photos and illustrations do not always show standard versions of machines.

The above information is a general description only, all information is supplied without liability.

